

Budget Analysis for the Acquisition of a class of Arctic/Offshore Patrol Ships

Erin Barkel & Rod Story

A/OPS Project Objectives

- · Scope:
 - 6 to 8 ice-capable patrol ships
- Schedule:
 - Begin construction September 2015
 - Project completion 2024
- Budget:
 - \$2.8 billion (i.e., \$3.1 billion less jetty infrastructure)





PBO Report Objectives

- Estimate the cost of building each ship
- Determine how many ships can be built within budget
- Estimate when the last ship will be completed
- Determine the impacts of project delays



METHODOLOGY





Assumptions


- includes development and production costs is calculated in "as spent" Canadian dollars
- assumes 3.3% annual escalation (1.3% above Bank of Canada target of 2%)
- assumes ship weight of 6,400 tonnes
- assumes more systems integration (i.e., communications equipment) than Svalbard
- assumes one development ship and 5 to 7 production systems (system is individual ships)
- assumes development began March 1, 2013 assumes construction of development ship will begin September 1, 2015 and will be no later than December 2018
- assumes the remaining ships will be completed by December 1, 2024
- assumes 10% profit on the contract
- assumes 15% HST on the contract





Model calibrated with Canadian-built, ice-capable, Coast Guard Ships

Ship Name	Complexity of Structure	Weight of Structure (lbs light)	Reported Cost (then-year million\$)
Louis St-Laurent	4.327	20,939,520	\$170
Henry Larsen	3.755	12,992,000	\$104
Amundsen	3.702	12,788,160	\$ 52
Des Groseilliers	3.648	12,613,440	\$ 65
Pierre Radisson	3.744	12,199,040	\$ 52
Griffon	3.719	4,883,200	\$ 14
Edward Cornwallis	3.634	7,403,200	\$ 60
Sir William Alexander	3.626	7,443,520	\$ 60
Ann Harvey	3.611	7,461,440	\$ 60
George R. Pearkes	3.640	7,479,360	\$ 60
Sir Wilfred Laurier	3.628	7,965,440	\$ 60
Martha L. Black	3.645	7,483,840	\$ 60
Samuel Risley	3.636	5,051,200	\$ 41
Earl Grey	3.619	4,977,280	\$ 41












Budget and scheduling implications of building only 4 A/OPS

- NSPS developed to eliminate boom and bust cycle which erodes yard capabilities
- A/OPS selected as "stepping stone" to CSC project
- If the CSC does not begin construction in 2021:
 - Early completion of A/OPS could cause the yard to wind-down prematurely
 - Labour efficiency could diminish
 - Lost opportunity to share yard overhead between projects









Questions?

THANK YOU

BACK-UP MATERIAL

Finding a link between qualitative data and TruePlanning inputs **Engineering Complexity** Qualitative 1. Similar to the Svalbard, but the design will be unique 2. Staffing ramp-up Scope of Design Effort Simple Modification, required to support 0.2 Existing Design Extensive NSPS workload Modification, Existing New Design, Existing <u>0.9</u> **1** Technology 1.2 1.4 Product Line New Design, Unfamiliar Technology 1.6 1.9 1.3 New Design, State of 1.9 Art Technology RAND, Sustaining Key Skills in the UK Naval Industry (2008)